

Proposal Date: 8/28/2024
Proposal #: 35112
Project: 35112-HOMETO...

Bill To:

City of League City
 Accounts Payable
 300 W Walker
 League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
GENERATOR	HOMETOWN HERO PARK 2024 ESTIMATE BUY BOARD 657-21 GENERATOR CUMMINS 250KW NATURAL GAS GEN C250N6Genset - Spark Ign, Natural Gas, 60Hz, 250kW1 ENGGTA855EICS, 383 HP, 8.5:1, Factory Certified for Emissions1 CATCatalyst, 5" Flange, NSPS 2/4/11 A331-2Duty Rating - Standby Power1 L090-2Listing - UL 22001 C002-2Natural Gas1 F266-2Enclosure - Sound Att, LEVEL 1, Galvaneal, Base Mtd, with Exhaust System1 P187-2Onan Green Enclosure Color1 B267-2Generator - S4L1D-C41 (ADS #TBD), 60Hz, Winding 311 - 12 Wire, 120C, 0.8pf1 R002-2Voltage - 277/480, 3ph1 B184-2Exciter / Regulator - PMG, 3 Phase Sensor1 A292-2Heater - Alternator, 120VAC1 KX21-2Set Control - Power Command 3.3 MLD1 H609-2Controls Facing Left1 E082-2Radiator Cooled1 H389-2Shutdown - Low Coolant Level1 H557-2Coolant Heater_40°F MinAmbientTemp1 E098-2Sightglass on Radiator1 A366-2Engine Governor - Electronic, Isochronous Only1	1		177,437.81	177,437.81

Total

Proposal Date: 8/28/2024
Proposal #: 35112
Project: 35112-HOMETO...

Bill To:

City of League City
 Accounts Payable
 300 W Walker
 League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
	A334-2Engine Starter - 24 VDC Motor1				
	A333-2Battery Charging Alternator - Normal Output1				
	D041-2Engine Air Cleaner - Normal Duty1				
	H706-2Lube Oil, Engine Filled Prior to Shipment1				
	H669-2Anti-Freeze - 50/50 Mix, System Filled Prior to Shipment1				
	A466-2Critical Grade Silencer, Carbon Steel1				
	H268-2Extension - Oil Drain1				
	E089-2Extension - Engine Coolant Drain1				
	H606-2Bargraph - AC Analog Meters1				
	0300-5929-02Annunciator (RS485)1				
	L050-2Manuals in English1				
	C8DXHBatteries - C8DXH Wet (QTY 2)2				
	F065-2Battery Rack1				
	A465-2Battery Charger, 120/240 VAC Input, 12A / 24V Output1				
	149-0751Fuel Strainer - Gaseous, 2in NPT1				
	MM-2-15Flexible Fuel Connection - Gaseous, 2in NPT1				
	KP74-2Switch - Emergency Stop, External1				
	H550-2Ground Fault Indicator w/ Alarm Output Contact1				
	M124-2Circuit Breaker - LSi_400A_100%, 600/525V1				
	L280-2Genset Warranty - Standby Power 2 year / 1000 hours1				

Total

Land & Sea Services 1, INC.

La Marque, TX 77568

Proposal

Proposal Date: 8/28/2024

Proposal #: 35112

Project: 35112-HOMETO...

Bill To:

City of League City
 Accounts Payable
 300 W Walker
 League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
	KM72-2Shunt Trip - 24VDC, Circuit Breaker1 KM69-2Aux Contacts - Form C, SPDT, Circuit Breaker1 OTECE, OTEC, NSER CUMMINS Transfer Switch-Electronic Control: 1200A OTEC1200, Transfer Switch- , PowerCommand, 1200 Amp Listing - UL 1008/CSA Certification Application - Utility to Genset Cabinet - Type 3R Cable Lugs - Mechanical, 4 - 600MCM/Pole Poles - 4 (Switched Neutral) Frequency - 60 Hz System - 3 Phase, 3 or 4 Wire Voltage - 480 Volts AC Genset Starting Battery - 24V DC PC40 Control Auxiliary Relay - Switch in Emergency Position - 24 Volts DC Auxiliary Relay - Switch In Normal Position - 24 Volts DC Interface - Communications Network, MODBUS RTU Module Relay - Elevator Signal Transfer Switch Warranty - 2 Year Comprehensive				

Total

Proposal Date: 8/28/2024
Proposal #: 35112
Project: 35112-HOMETO...

Bill To:
 City of League City
 Accounts Payable
 300 W Walker
 League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
LAND LABO...	LAND LABOR MECHANIC INSTALL GENERATOR FOUNDATION	1		7,000.00	7,000.00
Subcontract	PLUMBING FOR NATURAL GAS	1		5,000.00	5,000.00
Subcontract	CRANE	1		5,000.00	5,000.00
LAND LABO...	LAND LABOR MECHANIC SET PROGRAMS, START AND LOAD TEST SET UP ACUMEN PROVIDE TRAINING FOR GENERATOR FUNCTIONS	1		5,200.00	5,200.00
PARTS	ACUMEN REMOTE MONITORING	1		1,165.05	1,165.05
Subcontract	ELECTRICAL INSTALL & MATERIAL VALID FOR 30 DAYS	1		35,000.00	35,000.00
Total					\$235,802.86