

Proposal Date: 8/28/2024

Proposal #: 35208

Project: 35208-CITY HAL...

Bill To:

City of League City
Accounts Payable
300 W Walker
League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
GENERATOR	CITY HALL BUY BOARD 657-21				
	C300N6 CUMMINS Genset - Spark Ign, Natural Gas, 60Hz, 300kW1 ENG GTA855EICS, 470 HP, 8.5:0, Factory Certified for Emissions1 CAT Catalyst, 5" Flange, NSPS 2/4/11 A331-2Duty Rating - Standby Power1 L090-2Listing - UL 22001 C002-2Natural Gas1 F267-2Enclosure - Sound Att, LEVEL 2, Galvaneal, Base Mtd, with Exhaust System1 P187-2Onan Green Enclosure Color1 B267-2Generator - S4L1D-E41 (ADS #628), 60Hz, Winding 311 - 12 Wire, 120C, 0.8pf1 R098-2Voltage - 120/208, 3ph1 B184-2Exciter / Regulator - PMG, 3 Phase Sensor1 A292-2Heater - Alternator, 120VAC1 KX21-2Set Control - Power Command 3.3 MLD1 H609-2Controls Facing Left1 E082-2Radiator Cooled1 H389-2Shutdown - Low Coolant Level1 H557-2Coolant Heater_40°F MinAmbientTemp1 E098-2Sightglass on Radiator1 A366-2Engine Governor - Electronic, Isochronous Only1 A334-2Engine Starter - 24 VDC Motor1 A333-2Battery Charging Alternator - Normal Output1	1		241,054.95	241,054.95

Total

Land & Sea Services 1, INC.

La Marque, TX 77568

Proposal**Proposal Date:** 8/28/2024**Proposal #:** 35208**Project:** 35208-CITY HAL...**Bill To:**City of League City
Accounts Payable
300 W Walker
League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
	D041-2Engine Air Cleaner - Normal Duty1 H706-2Lube Oil, Engine Filled Prior to Shipment1 H669-2Anti-Freeze - 50/50 Mix, System Filled Prior to Shipment1 A466-2Critical Grade Silencer, Carbon Steel1 H268-2Extension - Oil Drain1 E089-2Extension - Engine Coolant Drain1 H606-2Bargraph - AC Analog Meters1 0300-5929-02Annunciator (RS485)1 L050-2Manuals in English1 739-2Remote HMI1 C8DXHBatteries - C8DXH Wet (QTY 2)2 F065-2Battery Rack1 A465-2Battery Charger, 120/240 VAC Input, 12A / 24V Output1 149-0751Fuel Strainer - Gaseous, 2in NPT1 MM-2-15Flexible Fuel Connection - Gaseous, 2in NPT1 KS53-2Signals-Aux, Input / Output1 KP74-2Switch - Emergency Stop, External1 H550-2Ground Fault Indicator w/ Alarm Output Contact1 M151-2Circuit Breaker - EMAX_800A_100%, 600/525V1 M251-2Circuit Breaker - EMAX_800A_100%, 600/525V1 L189-2Genset Warranty - Standby, 5 yr /				
Total					

Land & Sea Services 1, INC.

La Marque, TX 77568

Proposal**Proposal Date:** 8/28/2024**Proposal #:** 35208**Project:** 35208-CITY HAL...**Bill To:**

City of League City
Accounts Payable
300 W Walker
League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
	2500 hours parts, labor and travel1 KM72-2Shunt Trip - 24VDC, Circuit Breaker2 KM69-2Aux Contacts - Form C, SPDT, Circuit Breaker2 F997-02Std CB Mounting Option1 P997-2Drip Rails1 Fuel Train Kit1 OTECD, OTEC CUMMINS Transfer Switch-Electronic Control: 800A/1000A OTEC800, Transfer Switch, PowerCommand, 800 Amp Listing - UL 1008/CSA Certification Application - Utility to Genset Cabinet - Type 3R Poles - 3 (Solid Neutral) Frequency - 60 Hz System - 3 Phase, 3 or 4 Wire Voltage - 208 Volts AC Genset Starting Battery - 24V DC PC40 Control Auxiliary Relay - Switch in Emergency Position - 24 Volts DC Auxiliary Relay - Switch In Normal Position - 24 Volts DC Interface - Communications Network, MODBUS RTU Module Relay - Elevator Signal Transfer Switch Warranty - 5 Year Comprehensive				
Total					

Proposal Date: 8/28/2024

Proposal #: 35208

Project: 35208-CITY HAL...

Bill To:

City of League City
Accounts Payable
300 W Walker
League City TX 77573

Item	Description	Est. Hours/...	U/M	Rate	Total
LABOR	LABOR SET PROGRAMS, START AND LOAD TEST ACUMEN SET UP PROVIDE TRAINING FOR GENERATOR FUNCTIONS	1		5,200.00	5,200.00
PARTS	ACUMEN REMOTE MONITORING	1		1,165.05	1,165.05
Subcontract	ELECTRICAL MATERIALS & LABOR	1		55,000.00	55,000.00
Subcontract	CRANE	1		5,000.00	5,000.00
Subcontract	GENERATOR FOUNDATION	1		7,000.00	7,000.00
Subcontract	PLUMBING FOR GAS VALID FOR 30 DAYS	1		5,000.00	5,000.00
Total					\$319,420.00